

CHAPTER 11-1

PHOTOSYNTHESIS: THE PROCESS



Figure 1. *Antitrichia curtispendula* on a good photosynthetic day in late spring. Photo by Michael Lüth.

What Is Productivity?

In **primary productivity of plants**, solar energy is transformed to biomass. Using photosynthesis, green plants convert solar energy, carbon dioxide, and water to glucose and other carbon-based compounds and eventually to plant tissue. **Gross primary productivity** is the product of that photosynthetic fixation of carbon, whereas **net primary productivity** is the carbon that is actually converted into biomass, *i.e.*, the fixed carbon that remains once one subtracts that lost to respiration. Consider it like your income. The gross value is your salary, but the net is what is left after taxes, social security, and other "maintenance" deductions. Respiration is the maintenance tax the plant must pay from its gross carbon fixation.

Productivity might be considered the measure of success of a plant. As stated by Anderson *et al.* (1996), photosynthesis provides energy, organic matter, and oxygen for nearly all biotic processes, and it is the only renewable energy source on Earth. If productivity is reduced in the presence of another species, we assume a competitive interaction that deprives the species of some needed resource. Thus, we might think of productivity as being the central issue in ecology around which all other issues revolve.

In order to understand bryophyte productivity, it is necessary to understand the differences in the bryophyte

photosynthetic apparatus, especially the structure of the leaf or **phyllid**, compared to that of higher plants. I included the term phyllid here because technically, the bryophyte has no true leaves. This is because bryophytes lack lignified vascular tissue. However, few bryologists use the term phyllid, but rather have chosen to retain the term leaf, recognizing that the structure is different.

Early Studies

Much of our basic knowledge about the process of photosynthesis was learned through studies including bryophytes. In 1910, Blackman and Smith published their work on effects of CO₂ concentration on photosynthesis and respiration, including *Fontinalis antipyretica* (Figure 2) in the study. In fact, *F. antipyretica* was included in a number of early landmark studies (Plaetzer 1917; Harder 1921, 1923). One of the most important but overlooked of these early studies on bryophytes is the one by Bode (1940) in which he described a kind of respiration that occurred in the light and that was different from that occurring in the dark. He further described that the greatest respiration occurred in blue light and the greatest photosynthesis in red light. Dilks (1976) further elaborated on this **photorespiration** in bryophytes in a study of many species, demonstrating a lower rate of ¹⁴CO₂ loss in light compared

to dark that he attributed to partial reassimilation of the $^{14}\text{CO}_2$ produced, a partial inhibition of dark respiration by light, or a low rate of glycolate synthesis and oxidation. We now know that photorespiration typically is greater than dark respiration in **C₃ plants** (see below), and that dark respiration is suppressed in the light, and during the day it occurs mainly in darkened organs of plants, like roots.

In the higher plants, especially seed plants, photosynthesis occurs inside a complex leaf structure that both limits and protects its activity. Only the internal structures of the leaf are involved in photosynthesis, and these are protected by an epidermis on each surface. For photosynthesis to occur in these tracheophyte plants, CO_2 must enter the leaf, which it does through openings called stomata. This imposes a limit based on the capacity for holding gases and the speed with which the stomata can open to admit the gases. Furthermore, when the leaf begins to dry, the stomata close, thus ending the entry of new CO_2 .



Figure 2. *Fontinalis antipyretica*, the subject of many classical studies on photosynthesis. Photo by Michael Lüth.

The tracheophyte method of obtaining water can both limit and enhance tracheophyte photosynthesis. It means that the plant can obtain its water from the soil after the dew has gone and the rain has stopped. On the other hand, replacement of water, and its contained nutrients, is a somewhat slow process that can take minutes to hours following the addition of water by rainfall.

Bryophytes do not have these restrictions. The small size of a bryophyte leaf creates some fundamental differences in the way they achieve photosynthesis. Their ability to dry to 5-10% of their wet weight (Proctor 1990) and recover is unrivaled by most tracheophytes. Their one-cell-thick leaves have no epidermis, little or no waxy cuticle, and no stomata. Therefore, the photosynthetic cells are directly exposed to light for photosynthesis and have direct access to atmospheric gases. They furthermore have no midrib with lignified vascular conduction, but rather usually absorb their water directly through all their leaf surfaces. This means that they are able to respond to the addition of water from dew or fog and can immediately take advantage of a brief rainfall, but they have limited means of obtaining additional water from the soil to replenish that which is lost to evaporation and use. Nevertheless, many bryophytes do have a **costa**, which is the moss version of a midrib, and which at least in some

species can conduct limited amounts of water and most likely other substances as well. The role of the costa and other water-responsive cells has been discussed in the chapter on water.

With these gross morphological structures in mind, we can examine the internal workings of the photosynthetic organ, the leaf. It is here that most of the chlorophyll resides and it is here that most of the photosynthesis occurs.

Structural Adaptations

Based on the foregoing discussion of tracheophyte leaves, one might assume that a plant like *Marchantia* would be well adapted to photosynthesis. It has a thallus with tissue arranged like the spongy mesophyll of a maple leaf, abundant air chambers, pores surrounded by tiers of cells that function similarly to guard cells, and a cuticularized epidermis (Green & Snelgar 1982; Figure 3). But when compared to the functioning of a solid thallus in *Monoclea forsteri*, *Marchantia foliacea* achieves little photosynthetic advantage over the simple *Monoclea forsteri*. Furthermore, although the chambering of *Marchantia* provides an advantage for water relations, *Monoclea* still seems to have the photosynthetic advantage in very moist habitats. Woodward (1998) asked if plants really need stomata, and answered this question by citing evidence that the number per unit area has increased in geologic time as the CO_2 concentration has decreased. It would be interesting to see if the number of pores in thalli of the Marchantiaceae is affected by CO_2 concentration.



Figure 3. Cross section of the thallus of *Marchantia polymorpha* showing a pore and the chambered photosynthetic tissue beneath it. Photo with permission from <<http://www.botany.ubc.ca/bryophyte/LAB8.htm>>.

But our suggestion that internal spaces and an epidermis should benefit photosynthesis is not all wrong. Some bryophytes do benefit from added internal spaces that contribute to surface area for gas exchange. In *Polytrichum commune*, leaf lamellae increase the surface area 2.4-fold (Thomas *et al.* 1996). This seed plant "want-to-be" also has a waxy cuticle to prevent water loss and repels water that could block the movement of CO_2 into the leaf. Proctor (2005) demonstrated that this arrangement of lamellae seemed to protect these mosses from non-photochemical quenching that occurred in other mosses in exposed habitats. He showed that unistratose leaves are limited in their photosynthetic output by their CO_2

diffusion resistance, especially at high light levels. Mosses in the Polytrichaceae, on the other hand, enjoy more than a six-fold increase in leaf area, reducing the CO₂ diffusion constraint. The importance of these lamellae can be illustrated by *Atrichum undulatum* (Polytrichaceae) compared to non-polytrichaceous mosses (Krupa 1984). Leaves of this species had a higher photosynthetic rate per cm² than did leaves of *Rhizomnium punctatum* or *Funaria hygrometrica* with single-layered leaves. And the tiny *Aloina rigida* with succulent, lamellose leaves had a photosynthetic rate nearly 4.5 times that of *Funaria hygrometrica*, a moss of similar size.

Some species of *Polytrichum* have an additional adaptation. They have colorless margins that fold over the leaf lamellae (Figure 4). In alpine populations of *Polytrichum juniperinum*, this margin forms a greater part of the leaf than in the woodland populations. Bazzaz *et al.* (1970) suggested that this is an adaptation to the alpine habitat. This interpretation is consistent with the higher light saturation intensity for the alpine population (10,000 lux) compared to that of the woodland population (5000 lux).



Figure 4. Leaf cross section of *Polytrichum juniperinum* showing leaf lamellae and rolled over leaf edge. Photo by John Hribljan.

Mosses can actually change the structure of their chloroplasts in response to different **wavelengths** of light. In *Funaria hygrometrica*, the chloroplasts responded to red light by an increase in area and a decrease in thickness, shrinking in volume by about 10% (Zurzycki 1974). In low intensity of blue light, the effects were similar, but in high levels of blue light, there was a strong reduction of the surface area and a 35% shrinkage in volume. Both effects were reversible. In *Marchantia polymorpha*, far-red light at the end of the photoperiod caused 20-30% drop after only a 5-minute exposure following an 8-hour day for one week (Fredericq & DeGreef 1968). Longer days caused less reduction.

CO₂ concentration can also modify the size and shape of chloroplasts (Bockers *et al.* 1997). In *Marchantia polymorpha*, high CO₂ concentrations caused a modification of the chloroplast shape, and the cell had ~70% more chloroplasts. However, the chlorophyll content differed little, indicating that the greater number of chloroplasts exhibited less chlorophyll per chloroplast. The cells themselves were ~37% smaller in the high (2.0%) CO₂ concentrations compared to the 0.4% concentrations. These changes did not imbue the cells with any greater photosynthetic capacity or efficiency. Furthermore, the

CO₂ levels are very high compared to an atmospheric concentration of less than 0.04%, so the responses may be somewhat meaningless. Sonesson *et al.* (1992) reported only 0.04-0.045% CO₂ around *Hylocomium splendens* plants growing on soil.

Despite their small size, bryophytes respond to light much as do tracheophytes. Bryophytes increase their chlorophyll content as the light intensity decreases and increase their mean leaf area as light intensity increases (Sluka 1983).

Water is clearly a factor that limits photosynthesis. *Sphagnum* has a unique way of avoiding a water problem most of the time, making photosynthesis possible long after other bryophytes are too dry (Rice & Giles 1996). It maintains its own reservoir. Each photosynthetic cell is in contact with a large hyaline cell that holds water. When Rice (1995) compared three species pairs, the submerged member of the pair always had greater allocation to photosynthetic tissue and greater relative growth rates than did the non-aquatic member of the pair. This can be accomplished by allocating more tissue to photosynthetic cells rather than to hyaline cells and by increasing the light-harvesting chlorophyll proteins.

But obtaining CO₂ is especially problematic in the aquatic environment. In *Sphagnum*, reduction in the water-filled hyaline cells helps. Additional adaptations include larger, thinner branch leaves with fewer per length of branch, reducing the boundary layer resistance to CO₂ diffusion (Rice & Schuepp 1995). Aquatic photosynthetic cells have more surface exposure than those in leaves of above-water plants. A biochemical adaptation complemented this structural adaptation by a shift that favors light-reaction proteins (Rice 1995). Proctor *et al.* (1992) demonstrated that the Δ^{13} for *Sphagnum* photosynthetic cells with hyaline enclosure on both sides is significantly lower than for other terrestrial species, being consistent with the greater resistance to CO₂ uptake with increasing submersion.

Bryophytes have a variety of ways to trap air within or among the leaves. Interestingly, some of our evidence comes from fossils in amber (Robinson 1985). Fossil *Octoblepharum* shows trapped air in the leaves. Live *Sphagnum*, on the other hand, does not have air trapped in the hyaline cells – or does it? *Leucobryum* has large air bubbles in its hyaline cells, with bubbles that actually extend through many cells. Unlike *Octoblepharum*, *Leucobryum* leaves develop air pockets as they enlarge, but non-functional older leaves lose their air-entrapment ability. Furthermore, older leaves at the base of the plant use the hyaline cells to hold water.

One possibility to consider is that as air bubbles from photosynthesis form on the surfaces of the plants, CO₂ may enter the bubble by diffusion, much like the diving bell or the plastron used by some aquatic insects. But it would seem this would provide very small amounts indeed.

Photosynthetic Apparatus – the Chloroplast

Chloroplast Structure

Bryophytes, like tracheophytes and green algae (among others), have **chlorophylls a** and **b** and these chlorophyll molecules are organized within a complex

structure called the **chloroplast**. These two photosynthetic pigments are supplemented by the **chlorophyll antenna system** of **xanthophylls** and **carotenes** that serve to trap light energy and transfer it to the chlorophyll *a* action center, all within the **chloroplast**. In all plants and green algae, **starch** is stored within the chloroplast, but it will disappear after as little as 24 hours in darkness (Raven *et al.* 1992).

Chlorophyll in all plants resides in special double-membrane-bound structures called **chloroplasts** (Figure 5). These chloroplasts have within them stacks of membrane-bound structures called **thylakoids**, and it is within these thylakoid membranes and the surrounding fluid, the **stroma**, that the photosynthetic reactions take place (Figure 6).




Figure 5. Cells of *Fontinalis antipyretica* showing chloroplasts in cells. Photo by Janice Glime.




Figure 6. Structure of a single chloroplast. The chlorophyll molecules occur in the thylakoid membranes. Drawn by Janice Glime.

Associated Proteins

Associated with the chlorophyll molecules are proteins, known as **light-harvesting chlorophyll proteins (LHCP)**. There is some evidence that the protein association with chloroplasts in bryophytes might be unique. Aro (1982a) demonstrated differences in the protein complexes associated with photosystems I and II, using *Ceratodon purpureus*, *Pleurozium schreberi*, and *Marchantia polymorpha*. This is suggested by their ability to survive desiccation and freezing much more easily than plastids of tracheophytes (Tuba 1985). Further evidence came from their limited solubility in acetone when dry, but ability to dissolve much more easily if rehydrated for 15 seconds first (personal observation). Genetic evidence also supports the presence of chlorophyll proteins that are unique to bryophytes. *Marchantia polymorpha* has an *frxC* gene that codes for the sequence for an ATP-binding, Fe-protein that is a bacterial type not present in the tobacco chloroplast (Fujita *et al.* 1989). Furthermore, Neuhaus *et*

al. (1990) found only 94% sequence conservation of I polypeptide of Photosystem II between *Marchantia* and mustard (*Sinapis alba*).

Aro (1982b) compared bryophyte chlorophyll protein composition to that of duckweed (*Lemna*) and cucumber (*Cucurbita*). Both the moss *Ceratodon purpureus* and the thallose liverwort *Marchantia polymorpha* had more chlorophyll associated with the light-harvesting chlorophyll protein (LHCP) complexes and fewer with reaction center complexes than did the two tracheophytes. Harrer (2003) supported that observation with his study on *Marchantia polymorpha*, demonstrating that more than 50% of the PS II particles from *Marchantia polymorpha* carry one or two additional masses in the protein complex. So it is possible that bryophytes may have both differences in their kinds of chlorophyll protein, and have different amounts associated in different ways, giving their chlorophyll unique protection.

Fatty Acids

Valanne (1984) and Gellerman *et al.* (1972) have suggested that the C₂₀ polyunsaturated fatty acids increase the ability of mosses to adapt to extreme conditions. Those taxa living in shaded habitats have larger grana and contain even more polyunsaturated fatty acids than do sun-adapted species (Karunen & Aro 1979). It appears that polyunsaturated lipids play a role in maintaining structure and thermal stability of chloroplast membranes (Hugly *et al.* 1989), but little has been done to help us understand this relationship in bryophytes. Current studies on the genome and its function in the moss *Physcomitrella patens* and liverwort *Marchantia polymorpha* (e.g. Ikeuchi & Inoue 1988) are likely to help us understand these roles in the near future.

Need for Light

Color Retention in Dark

Light is required to make chlorophyll. In the dark, chlorophyll can degrade, and dry mosses can lose chlorophyll in the light. Hence, when bryophytes first encounter light after a prolonged period of darkness, one might expect them to be pale and have reduced photosynthetic activity. But Valanne (1977) found that protonemata of *Ceratodon purpureus* that had been in darkness for 1-2 months were able to produce starch within 30 minutes. Maximum photosynthesis, however, was not reached until the second day, providing enough time for the development of light-type chloroplasts. PS I had much higher activity in the dark-adapted protonemata than in that grown in light, whereas the activity of PS II was greater in light-grown protonemata.

Chloroplast Replication

Chloroplast replication requires light. Hahn and Miller (1966) demonstrated this in *Polytrichum commune* by showing that in the light chloroplasts replicated, but in the dark, chloroplasts would only replicate when sucrose was present in the medium. Rather, in continuous dark, and when given 15 minutes of far-red light per six hours, chloroplasts became larger. Electron micrographs revealed that the increase in size was due at least in part to the synthesis and degradation of starch.

Photosynthetic Capacity

In general, bryophytes are considered to have lower photosynthetic capacity than that of tracheophytes (Martin & Adamson 2001). In support of this, Rao *et al.* (1979) demonstrated that the Hill reaction (light-driven splitting of water in PS II) rates of three marchantialian liverworts are lower than those of seed plants. But Martin and Adamson (2001) have challenged this view. They too found that, when expressed on the basis of dry weight, net CO₂ uptake was considerably lower in mosses than in the six tracheophytes they studied. But the differences disappear when expressed on the basis of chlorophyll content. It would appear that the photosynthetic capacity of moss chloroplasts at light saturation and normal CO₂ levels is as great as that of tracheophytes.

One factor to be considered in the photosynthetic rate of bryophytes is their photosynthetic enzyme, ribulose biphosphate carboxylase/oxidase (RUBISCO). In a study by Rintamäki and Aro (1985) on a wide range of plant species, it was the moss *Ceratodon purpureus* (Figure 7), along with the grass *Deschampsia flexuosa*, that had the highest ratios of activity of RuBP carboxylase to RuBP oxidase, suggesting yet another adaptation for a high photosynthetic capacity. But *Ceratodon purpureus* is a sun moss and only one example. It is premature to generalize from this single study.



Figure 7. *Ceratodon purpureus*, a moss of sunny habitats and high RuBP carboxylase activity. Photo by Michael Lüth.

Antenna Pigments

The actual trapping of light energy results in a rapid spin on one of the electrons of a pigment. But this initial pigment need not be chlorophyll. Rather, it can be one of the pigments (chlorophyll *b*, carotene, xanthophyll) in the **chlorophyll antenna system** (Figure 8). These pigments occur in the thylakoid membranes within the chloroplasts and are part of Photosystem I and Photosystem II. This extra spin puts the electron in a higher energy state than before and the electron spins off the pigment molecule and is transferred to another and another of the pigment molecules until it reaches the reaction center, chlorophyll *a*.

The antenna pigments permit the chloroplasts to absorb energy in the regions where chlorophyll *a* has little ability to absorb. The two dimers of chlorophyll *a* absorb best at 680 and 700 nm and very poorly between 450 and 650 nm (Martínez Abaigar & Núñez Olivera 1998). Chlorophyll *b* helps to absorb in this latter range. The

carotenoids extend the absorption spectrum farther into the 450-490 nm range. Furthermore, **zeaxanthin**, a xanthophyll pigment, can deactivate singlet chlorophyll, and other carotenoids can deactivate both triplet chlorophylls and singlet oxygen that result from excess light energy. Thus, these serve as protective mechanisms against photo-inhibition and protect the chlorophylls from photooxidation, as discussed below.




Figure 8. Antenna pigments such as carotene, xanthophyll, and chlorophyll *b* in Photosystem I and Photosystem II transfer light energy to chlorophyll *a* within a single thylakoid membrane. Excitation of electrons in chlorophyll *a* occurs in both photosystems. Modified by Janice Glime from Goodwin & Mercer (1983) and Jensen & Salisbury (1984).

The most frequent of the antenna pigments in bryophytes include α - and β -carotene, lutein, zeaxanthin, violaxanthin, and neoxanthin (Taylor *et al.* 1972; Schmidt-Stohn 1977; Czezug 1980, 1985; Czezug *et al.* 1982; Huneck 1983; Farmer *et al.* 1988; Boston *et al.* 1991). Because these antenna pigments include yellow, orange, and sometimes red, as well as the different green of chlorophyll *b*, they are able to trap energy from different wavelengths of light instead of just the red that excites chlorophyll *a*. This is advantageous for the many species that inhabit locations that are low in red light. Among ~60 species tested, pigment types differ little between aquatic and terrestrial habitats (Martínez Abaigar & Núñez Olivera 1998). Among the exceptions is the unusual pigment **aurioxanthin** found in the obligate aquatic *Fontinalis antipyretica* (Bendz *et al.* 1968).

Heber *et al.* (2005) demonstrated that **zeaxanthin** was necessary for the dissipation of light energy in hydrated mosses. They suggest that only a few molecules of zeaxanthin are needed to suppress the excess energy at the dissipation centers in the antenna system of Photosystem II. Desiccation-dependent quenching, on the other hand, does not require zeaxanthin and apparently is a property of the reaction center complex of Photosystem II.

Many more antenna pigments actually exist among the bryophytes. In a single study on only ten species of liverworts, Czezug (1985) found nineteen carotenoids. In addition to the seven named above, he found lycopene, lycoxanthin, α -cryptoxanthin, β -cryptoxanthin, lutein epoxide, β -carotene epoxide, antheraxanthin, α -doradexanthin, adonixanthin, mutatoxanthin, rhodoxanthin, and apo-12'-violaxanthin. All but three of these pigments were already known from mosses. Of the three new ones, α -cryptoxanthin was known in algae, lichens, and higher plants, α -doradexanthin is common in Crustacea and fish,

and rhodoxanthin is known in club mosses, horsetails, ferns, conifers, and some species of the pondweed, *Potamogeton*.

Type of Photosynthetic Pathway

Among the tracheophytes, the **C₃ photosynthetic pathway** is most common, but some have a C₄ pathway, and some have a CAM pathway, neither of which seems to be available to bryophytes. These pathway names are based of the initial placement of the CO₂ when it is taken into the plant. The **C₃ pathway** is assumed to be the primitive pathway, known from algae and bryophytes, as well as tracheophytes, in which the carbon of CO₂ is fixed into a 3-carbon compound in its initial fixation within the plant. In tracheophytes, photosynthesis occurs in the mesophyll tissue of the leaf. There are no special adaptations for internal storage of the carbon for later use in photosynthesis – it must be used immediately and thus is placed immediately into the photosynthetic pathway to form PGA (phosphoglyceric acid; Figure 9), the 3-C compound. This immediate use is apparently characteristic of all bryophytes. This distinction of immediate use versus later use in photosynthesis is best understood by comparison with the other two pathways.




Figure 9. Melvin Calvin and associates found that the carbon from CO₂ is placed into RuBP to make a 6-carbon compound that immediately splits to form two molecules of 3-phosphoglycerate (PGA). This is the first step of the Calvin cycle and is the carbon fixation step for C₃ plants.

The **C₄ pathway** (only in tracheophytes) permits the storage of the carbon of CO₂ into a 4-carbon compound such as malic or oxalic acid in the mesophyll, and this compound can later be transported to the bundle sheath around the vascular tissue, where CO₂ is released and put into the photosynthetic pathway in the bundle sheath. The advantage here is that the stomata of a C₄ plant can remain open for a short time, CO₂ can be stored rapidly, and photosynthesis can continue for an extended period of time after the stomata are closed. Since the stomata are the major source of water loss from the plant, this is a tremendous savings in water loss and permits the plant to be more productive in dry regions than C₃ plants.

The **CAM pathway** is essentially a C₃ pathway except that the stomata open at night instead of in the daytime as in all other plants. Since photosynthesis cannot occur at night, the CAM plant survives because its carbon from CO₂

is stored in malic acid or other C₄ compound in the mesophyll for use in the daytime. However, in the CAM plant, the CO₂ is released in the mesophyll and photosynthesis takes place in the mesophyll tissue. Table 1 compares many of the structural and physiological attributes of plants with these three pathways.

As you can see from Table 1, each of these has certain ecological advantages and disadvantages. The C₃ pathway requires the least energy as ATP and is thus the most energy-efficient. The others, however, impart ecological advantages in hotter and/or drier climates and are more efficient in their use of CO₂.

Table 1. Comparison of tracheophyte plants with different types of CO₂ fixation. From Larcher (1983), compiled from many authors.

Characteristic	C ₃	C ₄	CAM
Leaf structure	Laminar mesophyll, parenchymatic bundle sheaths	Mesophyll arranged radially around chlorenchymatic bundle sheaths (Kranz-type anatomy)	Laminar mesophyll, large vacuole
Chlorophyll <i>a/b</i> CO ₂ -compensation concentration at optimal temperature	~3:1 30-70 μl l ⁻¹	~4:1 <10 μl l ⁻¹	<3:1 in light: 0-200 μl l ⁻¹ in dark: <5 μl l ⁻¹
Primary CO ₂ acceptor	RuBP	PEP	In light: RUBP in dark: PEP
First product of photosynthesis	C ₃ acids (PGA)	C ₄ acids (malate, aspartate)	In light: PGA in dark: malate
Photorespiration	Yes	Not measurable	Yes
Photosynthetic depression by O ₂	Yes	No	Yes
CO ₂ release in light (apparent photorespiration)	Yes	No	No
Net photosynthetic capacity	Slight to high	High to very high	In light: slight in dark: medium
Light-saturation of photosynthesis	At intermediate intensities	No saturation at highest intensities	At intermediate to high intensities
Temperature optimum	10-25°C	25-35°C	20-35°C?
Redistribution of assimilation products	Slow	Rapid	Variable
Dry-matter production	Medium	High	Low

In fact, some bryophytes are capable of photosynthesis at temperatures below freezing, and some species of *Fontinalis* (and probably others) have a temperature optimum near 5°C (Glime 1987a, b). Their light saturation point is less than full sunlight, and they are capable of net photosynthetic gain at very low light intensities (such as caves and deep water). These characteristics are unknown in C₄ plants. These capabilities greatly extend the growing season for mosses and undoubtedly contribute to their success in ecosystems such as the tundra and boreal forest.

In the aquatic system, CAM photosynthesis seems to be an adaptation of some tracheophytes to the low CO₂ concentration, permitting them to gain CO₂ at night when most of the algae and other aquatic plants are respiring CO₂. The cooler atmosphere may likewise contribute to a reduced loss of the CO₂ from the body of water. It is amazing to me to learn that the C₃ *Fontinalis antipyretica* has a higher carbon uptake rate than does the CAM plant

Isoetes bolanderi (Sandquist & Keeley 1990). Does this relate to its lack of cuticle and epidermis, permitting the immediate availability of CO₂ at any time of the day regardless of the light intensity? Perhaps a storage mechanism is not needed if uptake is always possible.

C₃ Evidence

Several studies have attempted to locate a pathway other than the C₃ pathway among bryophytes, examining the most likely deviants, the aquatic and xerophytic taxa. Thus far, there is no conclusive evidence for any pathway other than C₃. It appears that bryophytes have all the earmarks of C₃ plants, exhibiting higher CO₂ compensation points than those of tracheophytes (Rudolph 1990). Since C₃ plants are unable to sequester CO₂ and have only RUBISCO to help incorporate it into their photosynthetic pathway, they require higher concentrations of CO₂ than plants with C₄ or CAM pathways.

Raven *et al.* (1998) have reviewed the evidence for the C₃ pathway in bryophytes. Biochemically, bryophytes are C₃ plants, as far as is known. Their first carboxylation reaction accounts for more than 95% of the CO₂ incorporation. The ratio of *in vitro* RUBISCO carboxylase activity to that of *in vitro* PEP carboxylase activity is far higher than that known for C₄ or CAM plants (Rintamäki & Aro 1985; Farmer *et al.* 1986; Keeley *et al.* 1986). There is insufficient PEP carboxylase activity to support the observed photosynthetic carbon flux (Rintamäki *et al.* 1988; Madsen *et al.* 1993).

The CAM pathway can be excluded because there is no evidence of nighttime activity and there is no increase in acidity or accumulation of malic acid in the dark (Keeley & Morton 1982; Keeley *et al.* 1986; Raven *et al.* 1987).

Raven *et al.* (1987) then evaluated the physiological evidence, which is primarily based on the CO₂ compensation point. These data support the relatively high CO₂ compensation point of a C₃ plant (Fock *et al.* 1969; Ruttner 1947; Allen & Spence 1981; Raven *et al.* 1987).

Further evidence to support that bryophytes use a C₃ pathway comes from the ¹³C/¹²C discrimination values. Although there are difficulties with boundary layer resistance, especially in aquatic bryophytes, overall these values are consistent with a C₃ pathway (Raven *et al.* 1987, 1994; Keeley & Sandgren 1992; Rice & Giles 1994, 1996; Smith & Griffiths 1996a, b).

CO₂-concentrating Mechanisms – Exceptions to C₃?

Although bryophytes are considered C₃ plants (Rundel *et al.* 1979, James 1981; Raven *et al.* 1998), certain evidence makes us wonder if there are other variations among them. *Fissidens cf. mahatonensis* and *Fontinalis antipyretica* seem to have some sort of CO₂-concentrating mechanism (Salvucci & Bowes 1981; Raven *et al.* 1998). CO₂-concentrating mechanisms permit the plant to obtain CO₂ at a higher concentration than conditions would normally allow for a C₃ plant. This can be especially important for plants living in aquatic habitats with pH values in the range where the equilibrium shifts from CO₂ to bicarbonate or carbonate.

Raven (1991) summarized the ecological relationships of CO₂-concentrating mechanisms in plants. He found them to be negatively correlated with areas of CO₂ enrichment caused by respiration of organic carbon that

had been produced elsewhere, such as the respiration of bacteria and other organisms in sediments. Less pronounced relationships seem to exist with low temperatures during the growing season, low pH external to the plant, and rapid water movement over the plants that could replace the CO₂ as it is used in photosynthesis.

When growing submerged in Florida, USA, winter conditions (12°C, 10 h day length), *Fissidens cf. mahatonensis* had a typical C₃ compensation point (Salvucci & Bowes 1981). However, when grown in Florida summer conditions (30°C, 14 h day length), it had the ability to concentrate CO₂. This concentrating ability can be accomplished either by concentrating CO₂ around the RUBISCO to a greater concentration than that of the medium, using a C₄-like mechanism, or by using active transport of inorganic carbon across the membrane.

But *Fissidens cf. mahatoensis* is not the only aquatic moss that appears to have some sort of CO₂-concentrating mechanism. Peñuelas (1985) found two more aquatic mosses [*Fissidens grandifrons* (Figure 10) and *Fontinalis antipyretica*] that could carry out net photosynthesis in high inorganic carbon concentrations with high pH values that should have shifted the CO₂ – bicarbonate equilibrium toward the bicarbonate or carbonate end, providing less free CO₂ than that required to reach the compensation point. Several possibilities exist. As suggested earlier, there might be a mechanism for moving this inorganic carbon across the membrane by active transport. Or the moss could use its carbonic anhydrase (Steeman Nielsen & Kristiansen 1949; Arancibia & Graham 2003) externally to convert the HCO₃⁻ to free CO₂. I suggest a third possibility, that H⁺ ions available from cation exchange sites might be sufficient to lower the pH and shift the equilibrium toward CO₂ at the moss surface, despite the pH being too high elsewhere in the water for that shift to occur. The latter explanation would be consistent with the observations that the CO₂ compensation point and the ¹³C/¹²C discrimination values for central and Northern European populations of *Fontinalis antipyretica*, *Fissidens rufulus*, *Riccia fluitans*, and *Ricciocarpos natans* are consistent with a C₃ pathway (Ruttner 1947; Osmond *et al.* 1981; Allen & Spence 1981; Raven *et al.* 1987, 1994, 1998).



Figure 10. *Fissidens grandifrons*, a species of waterfalls and fast water, and often occurring in calcareous water with a high pH. Photo by Janice Glime.

This concentrating mechanism, whatever its nature, helps to explain the presence of bryophytes in calcareous

water of streams and lakes where the pH would suggest there would be insufficient free CO_2 for mosses to reach their CO_2 compensation point. And, in fact, some bryophytes of calcareous streams seem to be limited to waterfalls where high turbulence permits gaseous atmospheric CO_2 to come in contact with the moss surface.

One of the most intriguing finds is that *Fontinalis antipyretica* has a higher C uptake rate from the water column than does its CAM companion, *Isoetes bolanderi* (Sandquist & Keeley 1990). It appears that even aquatic bryophytes, contrasting with other aquatic macrophytes, lack or have only poorly developed CO_2 -concentrating mechanisms (Raven 1991). But what about *Fontinalis*? Steeman Nielsen and Kristiansen (1949) have demonstrated the presence of carbonic anhydrase in that genus. Is it able to concentrate CO_2 ? Can it convert bicarbonate to CO_2 , perhaps through a pH -lowering mechanism? And how should we explain the delay in carbon fixation in *Fontinalis antipyretica* (Søndergaard & Sand-Jensen 1979)? Aquatic plants like *Elodea* have internal air chambers that can delay the emission of respiratory CO_2 and slow the time from uptake to the time it actually enters photosynthesis. But *Fontinalis* has no air chambers. However, it has the lowest delay (0.2%) of the three plants tested, with *Elodea* having 8% and *Litorella* having 14%. Some researchers have treated this delay in *Fontinalis* as evidence of a concentrating mechanism, but the low percent seems insignificant.

In a separate comparison between the aquatic moss *Leptodictyum riparium* (Figure 11) and the tracheophyte *Elodea canadensis*, the moss had nearly double the RuBPCase activity (11.8 vs 6.0 $\mu M mg^{-1} chl h^{-1}$) of the tracheophyte, but also had approximately double the PEPcase activity (0.7 vs 0.3 $\mu M mg^{-1} chl h^{-1}$) (Keeley *et al.* 1986). Keeley *et al.* concluded that it is very unlikely that *Leptodictyum riparium* can utilize bicarbonate, whereas *Elodea* has been reported to use it freely.



Figure 11. *Leptodictyum riparium*, an aquatic moss. Photo by Michael Lüth.

Bicarbonate Uptake

Aquatic tracheophytes typically are able to take in bicarbonate for use in the photosynthetic pathway (Farmer *et al.* 1986). Some aquatic tracheophytes, in particular species of *Isoetes*, have a CAM photosynthetic pathway that permits them to take in CO_2 at night. But in their study of 15 species of aquatic macrophytes, Farmer *et al.* found that the aquatic moss *Fontinalis antipyretica* had no PEP

carboxylase, took in no CO_2 at night, and used RUBISCO for its photosynthetic CO_2 fixation. Steeman Nielsen (1947) stated outright that *Fontinalis antipyretica* "is unable to utilize HCO_3^- in the surrounding water for photosynthesis." On the other hand, Harder (1921) showed that as bicarbonate concentration increased from 0.01% to 0.64%, the assimilation plus respiration of *Fontinalis antipyretica* increased from 0.66 to 3.14. Burr (1941) likewise found that *Fontinalis* was more productive in water with bicarbonate than that with CO_2 . But what does this genus use as a mechanism to get its CO_2 , especially in water with a high pH where bicarbonates or carbonates predominate? Steeman Nielsen and Kristiansen (1949) suggested that there is evidence that CO_2 enters the photosynthetic reactions in hydrated form (bicarbonate?). But how is that accomplished?

Perhaps Peñuelas (1985) has discovered the differences behind these contrasting conclusions. He demonstrated that *Fontinalis antipyretica* from the River Muga in N.E. Spain was able to have a positive net photosynthesis up to a pH of 11.8-12.0 in a $NaHCO_3$ solution, a remarkably high pH and indicative of use of a carbon source other than that of CO_2 . Further support of this conclusion is that this population of *Fontinalis antipyretica* increased its photosynthetic rate when higher HCO_3^- concentrations at constant CO_2 were used. But in populations from other localities, this same researcher did not find evidence of its use of bicarbonates, suggesting that physiological races exist. This is consistent with my observations in eastern United States that this species is absent in limestone streams and streams with pH high enough to preclude free CO_2 , but in other parts of the world I have observed it growing on concrete and in alkaline streams.

Bain and Proctor (1980) tested twenty bryophytes from a variety of aquatic habitats to look for evidence of bicarbonate uptake. The ability of some bryophytes, such as *Scorpidium*, to live in water with high pH suggests that such a mechanism might exist. However, they found that the pH compensation points were in the range expected for C_3 plants dependent on free CO_2 for their carbon source. Only *Anthoceros husnotii* succeeded in having photosynthetic gain up to pH 9.5 in 2.0 mM $NaHCO_3$. For the others, the equilibrium clustered around pH 9.0 for 2.0 mM and 8.0 for 0.2 mM $NaHCO_3$. The four species of bicarbonate-using tracheophytes had final pH values ranging 10.1 – 10.9. As suggested above, there may be physiological races with different capabilities. The other possibility is that the mechanism for using bicarbonates may be inducible and was not sufficiently activated during the short-term lab experiments to make a difference. The slightly elevated pH compensation point for *Anthoceros husnotii* is consistent with other data on *Anthoceros* that suggests the **pyrenoids** have a role in concentrating CO_2 in some hornworts.

Pyrenoids

Members of the Anthocerotophyta (hornworts; Figure 12) with pyrenoids (*Anthoceros*, *Phaeoceros*) exhibit a well-developed ability to concentrate CO_2 (Raven 1997; Smith 2000). However, it appears that among land plants, only *Notothylas*, *Phaeoceros*, and *Anthoceros*, all members of the phylum Anthocerotophyta, have such a mechanism

(Smith & Griffiths 2000; Hanson *et al.* 2002). When a number of bryophytes were subjected to carbonic anhydrase inhibitors, only *Phaeoceros laevis*, a member of Anthocerotophyta, exhibited reduced CO₂ affinity and its CO₂ compensation point rose from 2.5 Pa to 20 Pa. No depression occurred in the other liverworts or mosses in the study. These results suggest the role of carbonic anhydrase as a CO₂-concentrating mechanism.

Raven *et al.* (1998) has reviewed the evidence supporting a CO₂-concentrating mechanism in the pyrenoids of some members of the Anthocerotophyta. Such a mechanism was already known in algae with pyrenoids (Vaughn *et al.* 1990, 1992). Pyrenoid-containing hornworts exhibited a ¹³C/¹²C discrimination of 7.2-11.7% compared to 16.4-35.1% in hornworts lacking pyrenoids (Smith & Griffiths 1996a, b). The higher values are consistent with a C₃ pathway, whereas the low values of the pyrenoid-containing hornworts are consistent with some sort of CO₂-concentrating mechanism. The CO₂ compensation point has only been investigated in *Anthoceros crispulus*, with a value of 26 μM CO₂ mole⁻¹, a value higher than that typical of C₄ plants, but lower than that for C₃ liverworts and mosses in the Smith and Griffiths studies (49-68 μM mole⁻¹).



Figure 12. *Phaeoceros carolinianus*. Photo by Michael Lüth.

Plants with a CO₂-concentrating mechanism have a higher affinity for external CO₂ than do typical C₃ plants. *Notothylas* and *Phaeoceros* exhibit CO₂ compensation points of 11-13 ppm CO₂ compared to 31 ppm for *Megaceros* and 64 ppm for *Marchantia polymorpha* (Hanson *et al.* 2002), where no concentrating mechanism seems to be present.

Those plants with a CO₂-concentrating mechanism can maintain a pool of CO₂ that is immediately available after a dark-light transition. *Anthoceros crispulus* exhibited a pool size of 17.6 μmol CO₂ g⁻¹ chlorophyll, whereas four of the five C₃ pathway bryophytes had no pool, and the thallose liverwort (with internal air chambers), *Conocephalum conicum* had only 5.5 μmol CO₂ g⁻¹ chlorophyll (Raven *et al.* 1998). *Notothylas* and *Phaeoceros* have an inorganic carbon pool of 19-108 μM g⁻¹ chlorophyll; *Megaceros* does not maintain any dissolved inorganic carbon pool (Hanson *et al.* 2002).

But what is this CO₂-concentrating mechanism? The concentrating mechanism of the pyrenoid suppresses the oxygenase activity of RUBISCO, hence reducing the loss of CO₂ and energy through photorespiration. We do not know the immediate CO₂-fixation products in these pyrenoid-bearing hornworts. Nor do we know the PEP

carboxylase to RUBISCO ratios. Is this some primitive C₄ plant struggling between relative amounts of PEP carboxylase and RUBISCO?

The Bottom Line

Nevertheless, no one has been able to demonstrate any direct evidence of a C₄ pathway, and consideration of a CAM pathway may be unreasonable since there are no stomata. Therefore, we can only infer certain characteristics of bryophyte photosynthetic physiology. Like the tracheophytes, we should expect them to have low photosynthetic temperature optima, ranging 10-20°C in most species. This is in part due to the loss of CO₂ beyond that gained in photosynthesis at higher temperatures. This loss is from photorespiration, which occurs only in light and increases with temperature more rapidly than does photosynthesis. C₄ plants either lack photorespiration or immediately grab the lost CO₂ and store it as malate. As C₃ plants, all mosses must have photorespiration and would therefore have more photosynthetic gain at low temperatures relative to C₄ plants. It appears that the first record of photorespiration in any plant was in the aquatic moss *Fontinalis* (Bode 1940), yet the best evidence we have for the possibility of an alternative pathway of CO₂ uptake in bryophytes is in this genus. The bottom line – we still don't understand how these CO₂ concentrating mechanisms work, especially in bryophytes lacking pyrenoids.

Diurnal Patterns in Photosynthesis?

Strong daily patterns exist in some bryophytes. *Pohlia wahlenbergii*, in a sub-alpine habitat in midsummer, had its highest light-saturated photosynthetic uptake early in the morning (8 mg CO₂ g⁻¹ hr⁻¹) (Coxson & Mackey 1990). By late afternoon, this had declined to ~5 mg CO₂ g⁻¹ hr⁻¹. The plants showed full recovery during late evening and nighttime. The authors considered that these daily oscillations could be recurring photodestruction and repair of the pigment complexes – an unusual response for plants in high light habitats such as this. They suggested that instead these fluctuations may represent a daily, endogenous photosynthetic rhythm as known in some phytoplankton populations. Although this is an intriguing idea that would permit the moss to gain CO₂ at a time when tracheophytes are slowed by the reduced light intensity and cool temperatures, much more evidence is needed to conclude that any endogenous rhythm exists.

I would be more inclined to attribute these morning and evening increases to the increased moisture in the atmosphere. In some parts of the world, fog and dew are the only sources of water for bryophytes. Bryophytes taken from a desiccator will rapidly gain weight on a balance as they absorb atmospheric moisture. A similar phenomenon may permit these plants to have low levels of photosynthetic gain in the low light but higher moisture levels of early morning and pre-dusk conditions.

Products of CO₂

Generally, textbooks present glucose as the final product of photosynthesis, but in fact, this is misleading. Photosynthesis makes PGA that can then be converted to a variety of products, glucose being one of them. In bryophytes, other products are likewise possible. Valanne

(1984) reported that the principal sugars made by bryophytes are sucrose, glucose, fructose, and mannose. She pointed out that evidence for notable exceptions in carbohydrate metabolism of bryophytes compared to that of tracheophytes is lacking (Allsopp 1951; Eschrich & Steiner 1967; Huneck 1969; Margaris & Kalaitzakis 1974; Valanne 1984). In the leafy liverwort *Plagiochila asplenioides*, volemitol, sucrose, and starch are the principal photosynthetic storage products (Suleiman & Lewis 1980).

In bryophytes, lipids are also an important photosynthetic product (Valanne 1984). In the Arctic, growing shoots typically contain more lipids than carbohydrates (Rastorfer 1972).

Koskimies-Soininen and Nyberg (1991) found that the types of lipids were dependent on temperature and light. In *Sphagnum fimbriatum*, the amount of total lipid increased in dim light conditions at both 15 and 25°C. Conversely, in darkness at 25°C the lipids decreased. Under normal light levels, a decrease in temperature in the range of 5-15°C causes a decrease in the amounts of linoleic, α -linolenic, and arachidonic acids. Concomitantly, there is an increase in the concentrations of palmitic, stearic, and oleic acids. When light intensity is also decreased, there is an increase in palmitic, stearic, linoleic, and arachidonic acids and a decrease in oleic and α -linolenic acids. Both temperature and light decreases elicit similar responses in total fatty acid desaturation and concentration of α -linolenic acid.

Dark CO₂ Fixation

These newly incorporated carbohydrates don't necessarily remain in the same products as are initially stored. In as little as two hours, a number of other products are possible. Within two hours in the leafy liverworts *Plagiochila asplenioides* (Figure 13) and *Scapania undulata* (Figure 13), the amino acids asparagine, glutamine, and glutamic acid were dominant products in both species (Gupta 1976). Citric acid and malic acids, along with an unknown acidic compound were also common in both. In addition, *Plagiochila* contained fumaric, glycolic, and succinic acids, although the fumaric and glycolic acids took longer than two hours to show ¹⁴CO₂. Soluble carbohydrates included sucrose, glucose, mannitol, fructose, and a series of fructans, differing little from the ones reported by Valanne (1984). But concentrations differ, with volemitol being the most labelled soluble carbohydrate in *Plagiochila asplenioides* and sucrose in *Scapania undulata*. Interestingly, malic acid, a product associated with CAM photosynthesis, was the most labelled organic acid in both species.

In the dark, non-photosynthetically fixed carbon is incorporated into amino acids (>60% of total non-photosynthetic carbon fixation), making primarily aspartate, alanine, and glutamate (Dhindsa 1985). Most of the remaining non-photosynthetic fixation incorporates carbon into organic acids (<40%). This dark fixation permits rehydrated mosses in the dark to repair damage due to desiccation.



Figure 13. **Upper:** *Plagiochila asplenioides*. **Lower:** *Scapania undulata*. Photo by Michael Lüth.

Transport of Photosynthate

Little is known about the movement of most substances in mosses and liverworts, but we do have evidence that both nutrients and photosynthate are indeed moved about. Alpert (1989) reported that within 26 hours, at least 10% of the photosynthate was translocated out of the leafy shoot of *Grimmia laevigata* (Figure 14).



Figure 14. *Grimmia laevigata*. Photo by Michael Lüth.

Transport of photosynthate in the bryophyte is often similar to that in tracheophytes. In *Polytrichastrum alpinum*, photosynthate is translocated from the above ground shoots to the rhizomes (Hobbs & Pritchard 1987). It does not move in the hydroids, but rather moves in the phloem-like leptoids, as demonstrated in *Polytrichum commune* (Eschrich & Steiner 1967). Héban (1975)

demonstrated that a cut stem will exude a clear liquid from the leptoids and associated parenchyma. The associated parenchyma cells seem to function much like companion cells of phloem. These cells have high enzyme activity and most likely are responsible for the movement of substances into and out of the leptoids (Richardson 1981).

While tracheophyte botanists are still trying to understand the mechanisms of xylem and phloem transport in the tracheophytes, bryologists are struggling with much smaller systems in bryophytes. One bryophyte stem is little larger than a single vascular bundle in one of these lignified plants. And the aphids that live on the fluids in the tracheophytes are larger than the diameters of bryophyte stems. So how do bryologists measure something so small when mechanisms of movement in its larger counterpart have been such an enigma for plant physiologists?

For measuring phloem transport, the old adage that if there is a niche, there is an insect to fill it, comes to the rescue of the bryologists. There are indeed tiny aphids (for example *Myzodium*) that live on the fluids in the phloem of *Polytrichum* species. And Bob Thomas, with his coworkers, has used them to help us understand how mosses transport things from place to place internally.

Thomas and coworkers (1990) found that *Polytrichum commune* transports things from source to sink, just as we find in those other plants. Through some of their early experiments, Thomas *et al.* (1988) found glucose, fructose, and sucrose in pulse-labelled stems 30 minutes after treatment in *Polytrichum commune*. The translocated carbon appeared in starch and cell wall polysaccharide pools within 1-6 weeks after treatment and could be used or stored. Perhaps the greater surprise is that 3.3% of the labelled sugar appeared later in neighboring stems, presumably following a source to sink gradient. This seems to be attributable to the transport of sugars in the leptome through perennating rhizomes, which often connect multiple stems.

But does it work the same way as in those other plants? Leaf conducting cells of *Polytrichum commune* have high solute concentrations, as revealed by incipient plasmolysis, and high ATPase activity at membrane surfaces (Thomas *et al.* 1990). Thomas and coworkers concluded that this permits the moss leaf to use a process analogous to **phloem loading** in minor veins of flowering plants. Furthermore, this sugar loading seems to be coupled with proton transport, suggesting a **proton pump** to get things across cell membranes.

Just how effective is this movement in transporting sugars and other substances from leaves to basal regions? Using petroleum jelly across leaf bases to prevent external capillary movement, Thomas and Lombard (1991) found that 17-38% of the translocated label could be detected in feeding aphids within four hours – not a very rapid rate by tracheophyte standards, where rates are more commonly about 30 cm per hour (Saupe 2005). In fact, the *Myzodium* had to divert nutrients away from the food conducting tissues of the stem and alter the normal source-to-sink flow in order to get enough. Even then, the aphids had to aggregate in order to compete with the natural source-to-sink travel within the moss. In *Polytrichastrum alpinum* (Figure 15), the photosynthate reached underground rhizomes at a rate of 3 mm h⁻¹ (Collins & Oechel 1974).

On the other hand, this moss can move things upward at 32 cm h⁻¹ (Eschrich & Steiner 1967).



Figure 15. *Polytrichastrum alpinum*. Photo by Michael Lüth.

All this discussion has been on Polytrichaceae! We know almost nothing beyond their successful lives to tell us about the other bryophytes in which the conducting system is less well developed. *Hylocomium splendens*, a predominately ectohydric moss, moved its photosynthate so slowly that 98% remained at the fixation site 48 hours later (Callaghan *et al.* 1978).

Skré *et al.* (1983) have helped to demonstrate some of the differences and consistencies between the endohydric Polytrichaceae and the more common ectohydric pattern of other mosses. *Polytrichum commune* behaved much like the C₄ plants and retained most of its labelled ¹⁴C after two hours. However, after 35 days it had sequestered a large portion (second highest of the four species) in its brown tissues. The ectohydric *Sphagnum subsecundum* retained the least of its labelled ¹⁴C, but moved the highest portion to its brown tissues after 35 days. *Hylocomium splendens* and *Pleurozium schreberi* had inconsistent patterns of translocation, but all four species accumulated ¹⁴C in their growing shoot tips and senescent brown tissues and all four experienced high losses of ¹⁴C through respiration during the peak summer growing season.

Storage of Photosynthate

Mosses and liverworts differ in their storage of photosynthate. In liverworts, sugar alcohols are important (Suleiman *et al.* 1979). In the mosses, the soluble product is primarily sucrose (Margaris & Kalaitzakis 1974; Suire 1975). Although most of the carbohydrates in aboveground portions of mosses are soluble sugars, the belowground parts are typically richer in starch (Hicklenton & Oechel 1977; Sveinbjörnsson & Oechel 1981). Witt and Teubert (1992) noted the contributions of phosphorylase in starch synthesis in all the sinks for starch in young gemmalings of the thallose liverwort *Riella helicophylla*. This included gemmae, meristems, and regenerating cells.

In *Polytrichum*, which may not be typical, the green, photosynthesizing shoot has the largest amount of nonstructural carbohydrate and the stem the least (Sveinbjörnsson & Oechel 1981). Sugars are highest in the green shoots; starches are highest in the belowground parts. The above ground portion can move more than 30% of its daily carbon gain to the below ground rhizome. In a more ectohydric *Dicranum fuscescens* (Figure 16), the green part of the shoot has ~7.0-10.5% ash-free tissue dry mass as

carbohydrate (Hicklenton & Oechel 1977), approximating about 0.7-1.3% of its fresh weight (Rastorfer 1972).



Figure 16. *Dicranum fuscescens*, showing lower, light brown, senescent portion near lower portion of picture on right. Photo by Michael Lüth.

As already seen, even senescent tissue is able to store carbon products (Skré *et al.* 1983). The senescent portion of *Dicranum elongatum* incorporates labelled carbon into lipids (Hakala & Sewón 1992). Hakala and Sewón concluded that the ability of the moss to transport such substances both upward and downward permitted this senescent portion of the moss to serve as an energy store. However, in *Dicranum fuscescens* little change is seen in the starch content of brown, senescing parts of the shoot, while the green, leafy part increases its total carbohydrate content during the growing season. Even so, the starch content of the leafy shoots of this species, as well as *Polytrichum commune* and *Polytrichastrum alpinum*, is less than 2% (Hicklenton & Oechel 1977), with similar values in *Pleurozium schreberi* and *Ceratodon purpureus* (Aro & Valanne 1979).

Sphagnum increases its lipid content in the spring in growing parts but decreases it in the senescent parts (Rastorfer 1972; Karunen & Salin 1981). *Dicranum elongatum*, on the other hand, stores large quantities of lipids in its senescent parts (Karunen & Mikola 1980; Karunen & Liljenberg 1981). In cold weather, mosses, at least in the Arctic, store high quantities of triglycerides (Karunen & Kallio 1976; Swanson *et al.* 1976; Karunen 1981; Karunen & Salin 1981). Both triglycerides and unsaturated fatty acids diminish in elevated temperatures (Karunen 1981).

Illumination affects the ratio of starch to protein, with *Pleurozium schreberi* and *Ceratodon purpureus* in continuous illumination showing an increase in starch content and decrease in protein in the leafy shoots (Aro & Valanne 1979).

During periods of darkness, both the older, senescent portions and active photosynthetic portions of the mosses can lose stored products. In *Racomitrium barbuloides*, the concentrations of ethanol-soluble sugars and lipids in green portions decreased in the dark, indicating their use as storage substances (Sakai *et al.* 2001). However, sugars and lipids in the brown, senescent portions did not decrease and starches remained constant in both portions. Continuous light caused initial increase of sugars and lipids in the green portion, but later these decreased in these

conditions. This regime caused a significant decline in photosynthetic capacity.

The type of carbohydrate stored determines its rate of turnover from storage. In the leafy liverwort *Plagiochila asplenioides*, breakdown of starch in the dark is rapid, but much carbon still remains as sucrose and volemitol due to their very slow turnover (Suleiman & Lewis 1980).

Sporophyte Photosynthesis

Although mature sporophytes are seldom green, they are typically green during the earlier stages of their development. This is easy to suppose in mosses, and confirmed in such mosses as *Funaria hygrometrica* (Krupa 1969), but liverworts do not elongate their setae until the sporophyte is mature, and the developing capsule is confined within the perianth (Figure 17). Nevertheless, Thomas *et al.* (1979) confirmed photosynthesis in liverwort sporophytes of *Fossombronia foveolata*, *Lophocolea heterophylla*, *Pellia epiphylla*, *Ptilidium pulcherrimum*, and *Riella affinis*. In the leafy liverwort *Lophocolea heterophylla*, 40% of this photosynthetic activity was attributable to spores. They confirmed that the gametophyte tissue surrounding the young sporophyte did inhibit the photosynthesis of the sporophyte by up to 50%.




Figure 17. *Scapania gracilis* illustrating the complete covering of the perianth over the immature capsule and loss of green color at maturity. Photo by Michael Lüth.

Krupa (1969) found that at certain stages in development, the sporophyte of *Funaria hygrometrica* is photosynthetically self-sufficient. Nurit and Chevallier (1978) confirmed this, finding that the *F. hygrometrica* gametophyte has a constant production of oxygen in the light throughout its development, but that the production of oxygen in the sporophyte decreases as the capsule matures. Although the weight of the seta decreases as the weight of the capsule increases in *Polytrichum*, this is not the case in *Funaria* (Paolillo & Bazzaz 1968), suggesting that in *Funaria* the capsule does its own photosynthesizing. Nevertheless, the gametophyte makes a major contribution to sporophyte biomass in bryophytes.

Atanasiu (1975) compared the gametophyte and sporophyte of *Dicranum scoparium* (Figure 18) and *Tortella tortuosa* (Figure 19). The ratios of net photosynthesis to dark respiration were 0.77-0.97 in the sporophyte and 3.50-5.17 in the gametophyte, suggesting little or no net photosynthetic gain by the sporophyte. These differences were supported by the determination that the gametophytes had 3-4 times the chlorophyll content of

the sporophytes. Atanasiu concluded that in these two species the sporophyte is not capable of supporting itself photosynthetically.



Figure 18. *Dicranum scoparium* gametophytes and sporophytes showing green capsules. Photo by Michael Lüth.



Figure 19. *Tortella tortuosa*. Photo by Michael Lüth.

Respiration

Bryophytes, like C_3 tracheophytes, have two types of respiration. The productivity of photosynthesis creates an environment in which ATP is produced and dark respiration is suppressed. This respiration, however, occurs in the dark to produce ATP and maintain the biological process of the plant. I am aware of no studies to determine if dark respiration occurs in rhizoids in the daytime, but one might suppose that it does, as it does in roots. But whereas photosynthesis suppresses dark respiration, the presence of the RUBISCO enzyme catalyzes not only photosynthesis, but also catalyzes photorespiration, both in the light. It is this photorespiratory process that causes C_3 plants to have such a low temperature optimum for net photosynthetic gain. As the temperature rises, the rate of photorespiration increases more rapidly than does the rate of photosynthesis, until ultimately the plant loses more CO_2 and energy than it gains. For example, in the High Arctic Svalbard populations of *Sanionia uncinata*, photosynthesis at near light saturation remained nearly constant in the range of 7 to 23°C, suggesting a Q_{10} near 1.0, but the respiratory Q_{10} in that range was 3.0 (Uchida *et al.* 2002). For this reason, most plants, including bryophytes, that have survived are

those that become dormant as the temperature rises, causing both process to cease. In bryophytes, this is often effected by drying that occurs at higher temperatures.

Even dark respiration, which is generally only about 1/2 to 1/3 that of photorespiration, can result in a significant carbon loss. In studying tropical bryophytes, Zotz *et al.* (1997) found that more than half the carbon gained by photosynthesis in the daytime was lost during the night as respiratory loss. This left the bryophytes to gain only about 45% of their initial carbon in new carbon per year. As is common, water was the primary limiting factor for carbon gain.



Figure 20. **Upper:** *Conocephalum conicum*. Photo by Michael Lüth. **Lower:** Cross section of thallus of *Conocephalum conicum* showing the pore, air chamber, and photosynthetic vs non-photosynthetic cells. Photo with permission from <<http://www.botany.ubc.ca/bryophyte/LAB8.htm>>.

In early experiments on the effects of light on respiration, Egle and Fock (1965) used, among others, the thallose liverwort *Conocephalum conicum* (Figure 20). They found that the results were similar in the liverwort and tracheophyte leaves, but that the curves for the liverwort were more pronounced. They learned that increasing oxygen concentrations (1, 25, & 75%) severely depressed photosynthesis. Following darkening, the CO_2 output increases steadily for about 5 minutes, at which time the stationary dark respiration rate is reached. Initially, high O_2 concentrations caused a strong burst of CO_2 in the dark, but within 15 minutes the thallus reaches the same equilibrium level of dark respiration. The level of oxygen from 1-99% does not influence the dark respiration. Higher light intensities increase the intensity of the CO_2 outburst at the onset of the next dark period. Using experiments that inhibited photosynthesis in the light, Egle and Fock demonstrated that the liberation of CO_2 in the light is greater than that in the dark. High O_2 concentrations cause this photorespiration to greatly exceed

the uptake of CO₂ by photosynthesis. Furthermore, old leaves exhibit more light respiration than do young leaves, contrasting with the reverse effect in dark respiration (Zelitch & Barber 1960; Fock 1965). Egle and Fock were convinced that this process was not the same respiratory process of decomposing assimilates that occurred in the dark. Rather, they discouraged the terminology "light respiration," considering that the light liberation of CO₂ might be only a side reaction of metabolism.

Peñuelas *et al.* (1988) compared the respiration rates of different parts of aquatic plants with that of the shoots of bryophytes. For the aquatic bryophytes studied, shoots had a respiratory rate of 53-66 μmol O₂ g⁻¹ dry mass h⁻¹. The green alga *Cladophora glomerata* had 96 μmol O₂ g⁻¹ dry mass h⁻¹ respiration. The algae and bryophytes had rates higher than those of flowering macrophyte stems (13-71 μmol O₂ g⁻¹ dry mass h⁻¹), but lower than that of their leaves (30-142 μmol O₂ g⁻¹ dry mass h⁻¹).

Summary

Net productivity is the photosynthetic gain, measured as CO₂ uptake or O₂ emission, of a plant, whereas gross photosynthesis is the total CO₂ fixation, frequently obtained by adding respiratory loss to measured CO₂ uptake. However, photorespiration occurs in the light and cannot be measured by the dark respiration method. Photorespiration, apparently first discovered in bryophytes, contributes to CO₂ loss, and its rate is generally higher than that of dark respiration.

Bryophyte photosynthesis can respond quickly to moisture from dew and fog as well as from rain. It likewise responds quickly to light. The structural simplicity of bryophyte leaves, with only a single cell layer and no need to bring CO₂ in through stomata that close in dry atmospheres, permits bryophytes to take advantage of photosynthetic opportunities immediately. In some cases, leaf lamellae increase the surface area and chlorophyll available for photosynthesis. Pores in some liverwort thalli may control CO₂ uptake. In some cases the chloroplast structure changes in response to changes in wavelengths of light.

Bryophyte chloroplasts are typical of plants, but their chlorophyll proteins and fatty acids appear to be somewhat different from those of tracheophytes. Furthermore, the chlorophyll is conserved for long periods in the dark, whereas it is not in tracheophytes.

Bryophyte productivity is generally low, but the photosynthetic capacity, when measured on the basis of chlorophyll concentration, is similar to that of tracheophytes.

The chlorophyll antenna system, as in tracheophytes, permits bryophytes to use and transmit energy in a variety of wavelengths, directing it to chlorophyll *a*. The most common of these antenna pigments are α- and β-carotene, lutein, zeaxanthin, violaxanthin, and neoxanthin.

Although some bryophytes seem to be able to enhance CO₂ uptake, for example through pyrenoids in many of the Anthocerotophyta, their photosynthetic pathway seems to be entirely C₃. Some aquatic bryophytes, such as *Fontinalis antipyretica*, seem to be able to take up CO₂ in high pH conditions that should

permit only very little free CO₂, suggesting some sort of concentrating mechanism.

Photosynthate is transported in the phloem, as demonstrated by tiny aphids. It can be stored in a variety of forms, particularly sugar alcohols (liverworts) and sucrose (mosses). Lipids may be stored in senescent portions and used later for spring growth.

Sporophytes of mosses are photosynthetically active in their young stages, but liverworts do not elongate their setae until the capsule matures, causing little light to reach the developing sporophyte.

Literature Cited

- Allen, E. D. and Spence, D. H. N. 1981. The differential ability of aquatic plants to utilize the inorganic C supply in freshwater. *New Phytol.* 87: 269-283.
- Allsopp, A. 1951. The sugars and non-volatile organic acids of some archegoniates. *J. Exper. Bot.* 1: 121-124.
- Alpert, P. 1989. Translocation in the nonpolytrichaceous moss *Grimmia laevigata*. *Amer. J. Bot.* 76: 1524-1529.
- Anderson, B., Salter, A. H., and Barber, J. 1996. *Molecular Genetics of Photosynthesis*. IRL Press at Oxford University, 252 pp.
- Arancibia, P. and Graham, L. 2003. Carbonic anhydrase in Charophyceae and bryophytes. Abstract. *Botany 2003, Aquatic and Wetland Plants: Wet & Wild*, Botanical Society of America, Mobile, p. 65.
- Aro, E.-M. 1982a. Polypeptide patterns of the thylakoid membranes of bryophytes. *Plant Sci. Lett.* 24: 335-345.
- Aro, E.-M. 1982b. A comparison of the chlorophyll-protein composition and chloroplast ultrastructure in two bryophytes and two higher plants. *Zeits. Pflanzenphysiol.* 108: 97-105.
- Aro, E.-M. and Valanne, N. 1979. Effect of continuous light on CO₂ fixation and chloroplast structure of the mosses *Pleurozium schreberi* and *Ceratodon purpureus*. *Physiol. Plant.* 45: 460-466.
- Atanasiu, L. 1975. Photosynthesis and respiration in sporophytes and gametophytes of two species of mosses. *Rev. Roum. Biol.* 20: 43-48.
- Bain, J. T. and Proctor, M. C. F. 1980. The requirement of aquatic bryophytes for free CO₂ as an inorganic carbon source: Some experimental evidence. *New Phytol.* 86: 393-400.
- Bazzaz, F. A., Paolillo, D. J. Jr., and Jagels, R. H. 1970. Photosynthesis and respiration of forest and alpine populations of *Polytrichum juniperinum*. *Bryologist* 73: 579-585.
- Bendz, G., Lööf, L. G., and Martensson, O. 1968. Moss pigments. 8. The carotenoids of *Fontinalis antipyretica* L. ex Hedw. *Acta Chem. Scand.* 22: 2215-2218.
- Blackman, F. F. and Smith, A. M. 1910-1911. Experimental researches on vegetable assimilation and respiration. IX.- On assimilation in submerged water-plants, and its relation to the concentration of carbon dioxide and other factors. *Proc. Roy. Soc. London Sec. B Biol. Sci.* 83: 389-412.
- Bockers, M., Capkova, V., Tich, I., and Schafer, C. 1997. Growth at high CO₂ affects the chloroplast number but not the photosynthetic efficiency of photoautotrophic *Marchantia polymorpha* culture cells. *Plant Cell Tiss. Organ Cult.* 48(2): 103-110.
- Bode, O. 1940. Assimilation, Atmung und Plastidenfarbstoffe in verschiedenfarbigen Licht aufgezogenen *Fontinalis*-Pflanzen. *Jahrb. Wiss. Bot.* 89: 208-244.

- Boston, H. L., Farmer, A. M., Madsen, J. D., Adams, M. S., and Hurley, J. P. 1991. Light-harvesting carotenoids in two deep-water bryophytes. *Photosynthetica* 25: 61-66.
- Burr, G. O. 1941. Photosynthesis of algae and other aquatic plants. In: Needham, J. G. Symposium on Hydrobiology. Univ. Wisc. Press, Madison. pp. 163-181.
- Callaghan, T. V., Collins, N. J., and Callaghan, C. H. 1978. Photosynthesis, growth, and reproduction of *Hylocomium splendens* and *Polytrichum commune* in Swedish Lapland. *Oikos* 31: 73-88.
- Collins, N. J. and Oechel, W. C. 1974. The pattern of growth and translocation of photosynthate in a tundra moss, *Polytrichum alpinum*. *Can. J. Bot.* 52: 355-363.
- Coxson, D. S. and Mackey, R. L. 1990. Diel periodicity of photosynthetic response in the subalpine moss *Pohlia wahlenbergii*. *Bryologist* 93: 417-422.
- Czeczuga, B. 1980. Investigation on carotenoids in Embryophyta. I. Bryophyta. *Bryologist* 83: 21-28.
- Czeczuga, B. 1985. Investigations on carotenoids in Embryophyta. III. Representatives of the Hepaticae. *Phyton* 25: 113-121.
- Czeczuga, B., Gutkowski, R., and Czerpak, R. 1982. Investigations of carotenoids in Embryophyta. II. Musci from the Antarctic. *Nova Hedw.* 36: 695-701.
- Dhindsa, R. S. 1985. Non-autotrophic CO₂ fixation and drought tolerance in mosses. *J. Exper. Bot.* 36: 980-988.
- Dilks, T. J. K. 1976. Measurement of the carbon dioxide compensation point and rate of loss of ¹⁴CO₂ in the light and dark in some bryophytes. *J. Exper. Bot.* 27: 98-104.
- Egle, K. and Fock, H. 1965. Light respiration – Correlations between CO₂ fixation, O₂ pressure and glycolate concentration. *Biochemistry of Chloroplasts*. Academic Press, London, pp. 79-87.
- Eschrich, W. and Steiner, M. 1967. Autoradiographische Untersuchungen zu Stofftransport bei *Polytrichum commune*. *Planta (Berlin)* 74: 330-349.
- Farmer, A. M., Boston, H. L., and Adams, M. S. 1988. Photosynthetic characters of a deepwater bryophyte from a clear, oligotrophic lake in Wisconsin, U.S.A. *Internat. Ver. Theor. Angew. Limnol. Verh.* 23: 1912-1915.
- Farmer, A. M., Maberly, S. C., and Bowes, G. 1986. Activities of carboxylation enzymes in freshwater macrophytes. *J. Exper. Bot.* 37: 1568-1573.
- Fock, H. 1965. Thesis, Science Faculty, University of Frankfurt/M.
- Fock, H., Krotov, G., and Canvin, D. T. 1969. Photorespiration in liverworts and leaves. In: Metzner, H. (ed.). *Progress in Photosynthesis I*. I. U. B. Tübingen, pp. 482-487.
- Fredericq, H. and Greef, J. De. 1968. Photomorphogenic and chlorophyll studies in the bryophyte *Marchantia polymorpha*. 1. Effect of red, far-red irradiations in short and long-term experiments. *Physiol. Plant.* 21: 346-359.
- Fujita, Y., Takahashi, Y., Kohchi, T., and Ozeki, H. 1989. Identification of a novel nifH-like (frxC) protein in chloroplasts of the liverwort *Marchantia polymorpha*. *Plant Molec. Biol.* 13: 551-561.
- Gellerman, J. L., Anderson, W. H., Richardson, F. G., and Schlenk, H. 1975. Distribution of arachidonic and eicosapentaenoic acids in the lipids of mosses. *Biochim. Biophys. Acta* 338: 277-290.
- Glime, J. M. 1987a. Growth model for *Fontinalis duriaei* based on temperature and flow conditions. *J. Hattori Bot. Lab.* 62: 101-109.
- Glime, J. M. 1987b. Phylogeographic implications of a *Fontinalis* (Bryopsida) growth model based on temperature and flow conditions for six species. *Mem. N. Y. Bot. Gard.* 45: 154-170.
- Goodwin, T. W. and Mercer, E. I. 1983. Phytohormones and related compounds. In: Goodwin, T. W. and Mercer, E. I. (eds.), *Introduction to Plant Biochemistry*, 2nd Ed., Pergamon Press, New York, pp. 567-626.
- Green, T. G. A. and Snelgar, W. P. 1982. A comparison of photosynthesis in two thalloid liverworts. *Oecologia* 54: 275-280.
- Gupta, R. K. 1976. Soluble constituents and photosynthetic products biosynthesized from ¹⁴CO₂ in leafy liverworts, *Plagiochila asplenoides* (L.) Dum. and *Scapania undulata* (L.) Dum. *Indian J. Exper. Biol.* 14: 595-598.
- Hahn, L. W. and Miller, J. H. 1966. Light dependence of chloroplast replication and starch metabolism in the moss *Polytrichum commune*. *Physiol. Plant.* 19: 134-141.
- Hakala, K. and Sewón, P. 1992. Reserve lipid accumulation and translocation of C¹⁴ in the photosynthetically active and senescent shoot parts of *Dicranum elongatum*. *Physiol. Plant.* 85: 111-119.
- Hanson, D., Andrews, T. J., and Badger, M. R. 2002. Variability of the pyrenoid-based CO₂ concentrating mechanism in hornworts (Anthocerotophyta). *Funct. Plant Biol.* 29: 407-416.
- Harder, R. 1921. Kritische Versuche zu Blackmans Theorie der begrenzenden Faktoren bei der Kohlensäureassimilation. *Jahrb. Wiss. Bot.* 60: 531-571.
- Harder, R. 1923. Bemerkungen über die variationsbreite des Kompensationspunktes beim Gaswechsel der Pflanzen. *Ber. Deutsch. Bot. Gesell.* 41: 194-198.
- Harrer, R. 2003. Associations between light-harvesting complexes and Photosystem II from *Marchantia polymorpha* L. determined by two- and three-dimensional electron microscopy. *Photosyn. Res.* 75(3): 249-258.
- Hébant, C. 1975. The phloem (leptome) of bryophytes. In: Aronoff, S., Dainty, J., Gorham, P. R., Srivastava, L. M., and Swanson, C. A. (eds.). *Phloem Transport*. Plenum Press, New York, pp. 211-224.
- Heber, U., Hedrich, R., and Shuvalov, V. A. 2005. Mechanisms of phototolerance in higher plants and poikilohydric organisms. Accessed 12 July 2005 at <<http://www.biozentrum.uni-wuerzburg.de/fileadmin/REPORT/BOT1/bot1004.htm>>.
- Hicklenton, P. R. and Oechel, W. C. 1977. Physiological aspects of the ecology of *Dicranum fuscescens* in the sub-arctic. II. Seasonal patterns of organic nutrient content. *Can. J. Bot.* 55: 2168-2177.
- Hobbs, V. J. and Pritchard, N. M. 1987. Population dynamics of the moss *Polytrichum piliferum* in north-east Scotland. *J. Ecol.* 75: 177-192.
- Hugly, S., Kunst, L., Browse, J., and Somerville, C. 1989. Enhanced thermal tolerance of photosynthesis and altered chloroplast ultrastructure in a mutant of *Arabidopsis* deficient in lipid desaturation. *Plant Physiol.* 90: 1134-1142.
- Huneck, S. 1969. Moosinhaltsstoffe, eine Übersicht. *J. Hattori Bot. Lab.* 32: 1-16.
- Huneck, S. 1983. Chemistry and biochemistry of bryophytes. In: Schuster, R. M. (ed.). *New Manual of Bryology*. Hattori Botanical Laboratory, Nichinan, pp. 1-116.
- Ikeuchi, M. and Inoue, H. 1988. A new Photosystem II reaction centre component (4.8-kDa protein) encoded by chloroplast genome. *Fed. Eur. Biochem. Soc. Lett.* 241: 99-104.

- James, T. A. 1981. Stable carbon isotope analysis of mosses and lichens growing in xeric and moist habitat. *Bryologist* 84: 79-81.
- Jensen, W. A. and Salisbury, F. B. 1984. *Botany*, 2nd ed. Wadsworth Publishing Co., Belmont, CA, 699 pp.
- Karunen, P. 1981. Role of neutral lipids in the physiology and ecology of subarctic *Dicranum elongatum*. *Can. J. Bot.* 59: 1902-1909.
- Karunen, P. and Aro, E. M. 1979. Fatty acid composition of polar lipids in *Ceratodon purpureus* and *Pleurozium schreberi*. *Physiol. Plant.* 45: 265-269.
- Karunen, P. and Kallio, P. 1976. Seasonal variation in the total lipid content of subarctic *Dicranum elongatum*. *Rep. Kevo Subarctic. Res. Stat.* 13: 63-70.
- Karunen, P. and Liljenberg, C. 1981. Content and fatty acid composition of steryl and wax esters in germinating spores of *Polytrichum commune*. *Physiol. Plant.* 53: 48-54.
- Karunen, P. and Mikola, H. 1980. Distribution of triglycerides in *Dicranum elongatum*. *Phytochemistry* 19: 319-321.
- Karunen, P. and Salin, M. 1981. Seasonal variation of lipids in *Sphagnum fuscum* surface peat. *Lindbergia* 7: 35-44.
- Keeley, J. E. and Morton, R. A. 1982. Distribution of diurnal acid metabolism in submerged aquatic plants outside the genus *Isoetes*. *Photosynthetica* 16: 546-553.
- Keeley, J. E. and Sandgren, D. R. 1992. Carbon: freshwater plants. *Plant Cell Environ.* 15: 1021-1035.
- Keeley, J. E., DeNiro, M. J., and Sternberg, L. O. 1986. The use of stable isotopes in the study of photosynthesis in freshwater plants. *Aquat. Bot.* 26: 213-223.
- Koskimies-Soininen, K. and Nyberg, H. 1991. Effects of temperature and light on the glycolipids of *Sphagnum fimbriatum*. *Phytochemistry* 30: 2529-2536.
- Krupa, J. 1969. Photosynthetic activity and productivity of the sporophyte of *Funaria hygrometrica* during ontogenesis. *Acta Soc. Bot. Poloniae* 38: 207-215.
- Krupa, J. 1984. Anatomical structure of moss leaves and their photosynthetic activity. *Acta Soc. Bot. Poloniae* 53: 43-51.
- Larcher, W. 1983. *Physiological Plant Ecology*, corrected printing of the second printing. Springer-Verlag, New York, 303 pp.
- Madsen, T. V., Enevoldsen, H. O., and Jorgensen, T. B. 1993. Effects of water velocity on photosynthesis and dark respiration in submerged stream macrophytes. *Plant Cell Environ.* 16: 317-322.
- Margaris, N. G. and Kalaitzakis, J. 1974. Soluble sugars from some Greek mosses. *Bryologist* 77: 470-472.
- Martin, C. E. and Adamson, V. J. 2001. Photosynthetic capacity of mosses relative to vascular plants. *J. Bryol.* 23: 319-323.
- Martínez Abaigar, J. and Núñez Olivera, E. 1998. Ecophysiology of photosynthetic pigments in aquatic bryophytes. In: Bates, J. W., Ashton, N. W., and Duckett, J. G. (eds.). *Bryology for the Twenty-first Century*. Maney Publishing and the British Bryological Society, UK, pp. 277-292.
- Murray, K. J., Tenhunen, J. D., and Nowak, R. S. 1993. Photoinhibition as a control on photosynthesis and production of *Sphagnum* mosses. *Oecologia* 96: 200-207.
- Neuhaus, H., Pfannschmidt, T., and Link, G. 1990. Nucleotide sequence of the chloroplast psbl and trnS-GCU genes from mustard (*Sinapis alba*). *Nucleic Acids Res.* 18: 368.
- Nurit, F. and Chevallier, D. 1978. La sporogenese chez *Funaria hygrometrica*: Etude oxygraphique en rapport avec les modifications ultrastructurales. In *Congres International de Bryologie, Bryophytorum Bibliotheca* 13: 195-209.
- Oechel, W. C. 1976. Seasonal patterns of temperature response of CO₂ flux and acclimation in Arctic mosses growing *in situ*. *Photosynthetica* 10: 447-456.
- Osmond, C. B., Valanne, N., Haslam, S. M., Votila, P., and Roksandic, Z. 1981. Comparisons of δ¹³C values in leaves of aquatic macrophytes from different habitats in Britain and Finland: Some implications for photosynthetic processes in aquatic plants. *Oecologia* 50: 117-124.
- Paolillo, D. J. Jr. and Bazzaz, F. A. 1968. Photosynthesis in sporophytes of *Polytrichum* and *Funaria*. *Bryologist* 71: 335-343.
- Patidar, K. C., Solanki, C. M., and Kaul, A. 1986. Chlorophyll concentration and *a/b* ratios in response to habitats in three species of *Riccia*. *Yushania* 3: 1-4.
- Peñuelas, J. 1985. HCO₃⁻ as an exogenous carbon source for aquatic bryophytes *Fontinalis antipyretica* and *Fissidens grandifrons*. *J. Exper. Bot.* 36: 441-448.
- Peñuelas, J., Murillo, J., and Azcon-Bieto, J. 1988. Actual and potential dark respiration rates and different electron transport pathways in freshwater aquatic plants. *Aquat. Bot.* 30: 353-362.
- Plaetzer, H. 1917. Untersuchungen über die Assimilation und Atmung von Wasserpflanzen. *Phys. Med. Gesel (Wurzburg)* 45: 31-101.
- Proctor, M. C. F. 1990. The physiological basis of bryophyte production. *International Symposium on Bryophyte Ecology Edinburgh (UK), 19-22 Jul 1988*. *J. Linn. Soc. Bot.* 104: 61-77.
- Proctor, M. C. F. 2005. Why do Polytrichaceae have lamellae? *J. Bryol.* 27: 221-229.
- Proctor, M. C. F., Raven, J. A., and Rice, S. K. 1992. Stable carbon isotope discrimination measurements in *Sphagnum* and other bryophytes: Physiological and ecological implications. *J. Bryol.* 17: 193-202.
- Rao, K. R., Kumar, N. R., and Reddy, A. N. 1979. Studies of photosynthesis in some liverworts. *Bryologist* 82: 286-288.
- Rastorfer, J. R. 1972. Comparative physiology of four west Antarctic mosses. *Antarct. Res. Ser.* 20: 143-161.
- Raven, J. A. 1991. Implications of inorganic carbon utilization: Ecology, evolution, and geochemistry. *Can. J. Bot.* 69: 908-924.
- Raven, J. A. 1997. Inorganic carbon acquisition by marine autotrophs. *Adv. Bot. Res.* 27: 85-209.
- Raven, J. A., Griffiths, H., Smith, E. C., and Vaughn, K. C. 1998. New perspectives in the biophysics and physiology of bryophytes. In: Bates, J. W., Ashton, N. W., and Duckett, J. G. (eds.). *Bryology in the Twenty-first Century*. Maney Publishing and the British Bryological Society, UK, pp. 261-275.
- Raven, J. A., Johnson, A. M., Newman, J. R., and Scrimgeour, C. M. 1994. Inorganic carbon acquisition by aquatic photolithotrophs of the Dighty Burn, Angus, UK: Uses and limitations of natural abundance measurements of carbon isotopes. *New Phytol.* 127: 271-286.
- Raven, J. A., MacFarlane, J. J., and Griffiths, H. 1987. The application of carbon isotope techniques. In: Crawford, R. M. M. (ed.). *Plant Life in /aquatic and Amphibious Habitats*. British Ecological Society Special Symposium, Blackwell, Oxford, pp. 129-144.
- Raven, P. H., Evert, R. F., and Eichhorn, S. E. 1992. *Biology of Plants*. Worth Publishers, New York, p. 21.
- Rice, S. K. 1995. Patterns of allocation and growth in aquatic *Sphagnum* species. *Can. J. Bot.* 73: 349-359.
- Rice, S. K. and Giles, L. 1994. Climate in the Pleistocene. *Nature* 371: 111.

- Rice, S. K. and Giles, L. 1996. The influence of water content and leaf anatomy on carbon isotope discrimination and photosynthesis in *Sphagnum*. *Plant Cell Environ.* 19: 118-124.
- Rice, S. K. and Schuepp, P. H. 1995. On the ecological and evolutionary significance of branch and leaf morphology in aquatic *Sphagnum* (Sphagnaceae). *Amer. J. Bot.* 82: 833-846.
- Richardson, D. H. S. 1981. *The Biology of Mosses*. John Wiley & Sons, New York, 220 pp.
- Rintamäki, E. and Aro, E.-M. 1985. Photosynthetic and photorespiratory enzymes in widely divergent plant species with special reference to the moss *Ceratodon purpureus*: properties of ribulose biphosphate/oxygenase, phosphoenolpyruvate carboxylase and glycolate oxidase. *J. Exper. Bot.* 36: 1677-1684.
- Rintamäki, E., Keys, A. J., and Parry, M. A. J. 1988. Comparison of the specific activity of ribulose-1,5 bisphosphate carboxylase-oxygenase from some C₃ and C₄ plants. *Physiol. Plant.* 74: 323-331.
- Robinson, H. 1985. The structure and significance of the leucobryaceous leaf. *Monogr. Syst. Bot. Missouri Bot. Gard.* 11: 111-120.
- Rudolph, H. 1990. Biochemical and physiological aspects of bryophytes. In: Zinsmeister, H. D. and Mues, R. (eds.). *Bryophytes, Their Chemistry and Chemical Taxonomy, Proceedings of the Phytochemical Society of Europe 29*, Oxford University Press, Oxford, pp. 227-252.
- Rundel, P. W., Stichler, W., Zander, R. H., and Ziegler, H. 1979. Carbon and hydrogen isotope ratios of bryophytes from arid and humid regions. *Oecologia (Berlin)* 44: 91-94.
- Ruttner, F. 1947. Zur Frage der Karbonatassimilation der Wasserpflanzen, I. *Österr. Bot. Zeits.* 94: 265-294.
- Sakai, N., Nakatsubo, T., Kanda, H., and Masuzawa, T. 2001. Carbon storage and photosynthetic capacity of the moss *Racomitrium barbulooides* Card. under various light conditions. *Hikobia* 13: 327-334.
- Salvucci, M. E. and Bowes, G. 1981. Induction of reduced photorespiration activity in submersed and amphibious aquatic macrophytes. *Plant Physiol.* 67: 335-340.
- Sandquist, D. R. and Keeley, J. E. 1990. Carbon uptake characteristics in two high elevation populations of the aquatic CAM plant *Isoetes bolanderi* (Isoetaceae)[sic]. *Amer. J. Bot.* 77: 682-688.
- Saupe, Stephen G. 2005. *Plant Physiology (Biology 327)*. Accessed on 4 January 2007 at <<http://employees.csbsju.edu/SSAUPE/biol327/Lecture/phloem.htm>>.
- Schmidt-Stohn, G. 1977. Aenderungen der plastidenpigmente bei *Sphagnum magellanicum* Brid. in Abhaengigkeit von Standort, Verfaerbungsgrad und Alter. *Zeits. Pflanzenphysiol.* 81: 289-303.
- Skré, O., Oechel, W. C., and Miller, P. M. 1983. Patterns of translocation of carbon in four common moss species in a black spruce (*Picea mariana*) dominated forest in interior Alaska. *Can. J. Forest Res.* 13: 869-878.
- Sluka, Z. A. 1983. The dependence of the chlorophyll content and the leaf-area of mosses on the ecological conditions. *Vest. Mosk. Univ. Ser. XVI Biol.* 37(3): 24-29.
- Smith, E. 2000. The role of the photosynthetic carbon concentrating mechanism in bryophytes. *Bull. Brit. Bryol. Soc.* 74: 18-19.
- Smith, E. C. and Griffiths, H. 1996a. The occurrence of the chloroplast pyrenoid is correlated with the activity of a CO₂-concentrating mechanism and carbon isotope discrimination in lichens and bryophytes. *Planta* 198: 6-16.
- Smith, E. C. and Griffiths, H. 1996b. A pyrenoid-based carbon-concentrating mechanism is present in terrestrial bryophytes of the class Anthocerotae. *Planta* 200: 203-212.
- Smith, E. C. and Griffiths, H. 2000. The role of carbonic anhydrase in photosynthesis and the activity of the carbon-concentrating-mechanism in bryophytes of the class Anthocerotae. *New Phytol.* 145: 29-37.
- Søndergaard, M. and Sand-Jensen, K. 1979. The delay in ¹⁴C fixation rates by three submerged macrophytes, a source of error in the ¹⁴C technique. *Aquat. Bot.* 6: 111-119.
- Sonesson, M., Gehrke, C., and Tjus, M. 1992. CO₂ environment, microclimate and photosynthetic characteristics of the moss *Hylocomium splendens* in a subarctic habitat. *Oecologia* 92: 23-29.
- Steeman Nielsen, E. 1947. Photosynthesis of aquatic plants with special reference to the carbon source. *Dansk. Bot. Ark.* 12(8): 1-71.
- Steeman Nielsen, E. and Kristiansen, J. 1949. Carbonic anhydrase in submersed autotrophic plants. *Physiol. Plant.* 2: 325-331.
- Suire, C. 1975. Les donnees actuelles sur la chimie des bryophytes. *Rev. Bryol. Lichenol.* 41: 105-256.
- Suleiman, A. A. A. and Lewis, D. H. 1980. Carbohydrate metabolism in the leafy liverwort, *Plagiochila asplenioides* (L.) Dum. var. *major* Nees. *New Phytol.* 84: 45-58.
- Suleiman, A. A. A., Bacon, J., Christie, A., and Lewis, D. H. 1979. The carbohydrates of the leafy liverwort *Plagiochila asplenioides* (L.) Dum. *New Phytol.* 82: 439-448.
- Sveinbjörnsson, B. and Oechel, W. C. 1981. Controls on carbon dioxide exchange in two *Polytrichum* moss species, 2. The implications of belowground plant parts on the whole plant carbon balance. *Oikos* 36: 348-354.
- Swanson, E. S., Anderson, W. H., Gellerman, J. L., and Schlenk, H. 1976. Ultrastructure and lipid composition of mosses. *Bryologist* 79: 339-349.
- Taylor, A. O., Jesper, N. M., and Christeller, J. T. 1972. Plants under climatic stress. III. Low temperature, high light effects on photosynthetic products. *Plant Physiol.* 47: 798-802.
- Thomas, R. J. and Lombard, C. S. 1991. Aphid infestation and its effects on translocation in *Polytrichum commune*. *Bryologist* 94: 1-4.
- Thomas, R. J., Ryder, S. H., Gardner, M. I., Sheetz, J. P., and Nichols, S. D. 1996. Photosynthetic function of leaf lamellae in *Polytrichum commune*. *Bryologist* 99: 6-11.
- Thomas, R. J., Schiele, D. M., and Damberg, D. T. 1990. Translocation in *Polytrichum commune* (Bryophyta). II. Clonal integration. *Amer. J. Bot.* 77: 1569-1573.
- Thomas, R. J., Schiele, E. M., and Scheirer, D. C. 1988. Translocation in *Polytrichum commune* (Bryophyta) I. Conduction and allocation of photoassimilates. *Amer. J. Bot.* 75: 275-281.
- Thomas, R. J., Stanton, D. S., and Grusak, M. A. 1979. Radioactive tracer study of sporophyte nutrition in hepatics. *Amer. J. Bot.* 66: 398-403.
- Tuba, Z. 1985. Photosynthetic pigment responses in *Tortula ruralis* during daily desiccation. *Abstr. Bot.* 9, Suppl. 2: 231-239.
- Uchida, M., Muraoka, H., Nakatsubo, T., Bekku, Y., Ueno, T., Kanda, H., and Koizumi, H. 2002. Net photosynthesis, respiration, and production of the moss *Sanionia uncinata* on a glacier foreland in the High Arctic, Ny-Ålesund, Svalbard. *Arct. Antarct. Alp. Res.* 34: 287-292.

- Valanne, N. 1977. The combined effects of light intensity and continuous light on the CO₂ fixation, chlorophyll content and chloroplast structure of the protonema of *Ceratodon purpureus*. *Zeit. Pflanzenphysiol.* 83: 275-283.
- Valanne, N. 1984. Photosynthesis and photosynthetic products in mosses. In: Dyer, A. F. and Duckett, J. G. (eds.). *The Experimental Biology of Bryophytes*, Academic Press, New York, pp. 257-274.
- Vaughn, K. C., Campbell, E. G., Hasegawa, J., Owen, H. A., and Renzaglia, K. S. 1990. The pyrenoid is the site of ribulose 1,5-bisphosphate carboxylase/oxygenase accumulation in the hornwort (Bryophyta: Anthocerotae) chloroplast. *Protoplasma* 156: 117-129.
- Vaughn, K. C., Ligrone, R., Owen, H. A., Hasegawa, J., Campbell, E. O., Renzaglia, K. S., and Monge-Najera, J. 1992. The anthocerote chloroplast: a review. *New Phytol.* 120: 169-190.
- Witt, H.-J. and Teubert, B. 1992. Changes in activities of enzymes involved in starch metabolism during the development of gemmae to 14-day-old plants of *Riella helicophylla*. *J. Plant Physiol.* 140: 375-377.
- Woodward, F. I. 1998. Do plants really need stomata? *J. Exper. Bot.* 49 (spec. iss.): 471-480.
- Zelitch, I. and Barber, G. A. 1960. In: Egle, K. and Fock, H. 1965. Light respiration – Correlations between CO₂ fixation, O₂ pressure and glycollate concentration. *Biochemistry of Chloroplasts*. Academic Press, London, pp. 79-87.
- Zotz, G. and Rottenberger, S. 2001. Seasonal changes in diel CO₂ exchange of three central European moss species: A one-year field study. *Plant Biol.* 3: 661-669.
- Zotz, G., Büdel, B., Meyer, A., Zellner, H., and Lange, O. L. 1997. Water relations and CO₂ exchange of tropical bryophytes in a lower montane rain forest in Panama. *Bot. Acta* 110: 9-17.
- Zurzycki, J. 1974. The effect of blue and red radiation on the volume changes of *Funaria* chloroplasts in vivo. *Photosynthetica* 8: 338-343.